



NOTES:

1. IF, WHEN THE DAMAGED PORTION OF THE EXISTING MAIN IS REMOVED, SATURATED SOIL IS FOUND, THE SATURATED SOIL SHALL BE EXCAVATED, REMOVED FROM THE SITE AND REPLACED WITH IMPORTED BEDDING MATERIAL MEETING CURRENT PIMA COUNTY WASTEWATER MANAGEMENT STANDARDS.
2. ALL SEWER REPAIRS SHALL BE INSPECTED BY PCWMD OR AUTHORIZED REPRESENTATIVE PRIOR TO BACKFILL.
3. COMPACTION OF BACKFILL SHALL BE IN ACCORDANCE WITH SECTION 508 OF THE PIMA COUNTY/CITY OF TUCSON STANDARD SPECIFICATIONS FOR PUBLIC IMPROVEMENTS.

ISSUED:		STANDARD DETAIL		DETAIL NO.
8/92		SEWER MAIN REPAIR		WWM 102
REVISED:				SHEET 1 OF 1
7/02				